

---

# AP2 & Debuncher Acceptance

Keith Gollwitzer  
Dept. of Energy Review  
February 25, 2004

---


# Outline

---

- Overview of Goal
- Plan and Status
  - What is new
    - Near completion of aperture documentation
    - Survey as found been performed
    - LBNL study of AP2 and chromatic effects
    - AP2 BPM characterization and studies
    - New Debuncher BPM Data Acquisition
    - Moved DRF3 cavity from dispersion region
    - Change of D4Q4 from build to use existing spares
    - Debuncher extraction kicker as limitation
    - Additional motorized Debuncher quad stands installed
    - Developing "Paint the Aperture" procedure
    - Developed new combined AP2+Deb admittance measurements performed during stacking.

- 
- Overview of Beam Studies & Schedule
- AP2 & Debuncher Acceptance - Keith Gollwitzer

# Goal: Lots of Pbars to Circulate in Deb.



$< 20\pi$  mm-mrad

$20\pi-40\pi$  mm-mrad

$> 40\pi$  mm-mrad

Simulation of pbar transverse phase space (both planes) out of a 750 T/m lens.  
{2 entries for each pbar that traverses only Lithium part of lens}

*$35\pi$  mm-mrad aperture allows  $320\pi$  mm-mrad beam emittance*

Collect as much as possible for Debuncher Cooling Systems

# Realization of $35\pi$ mm-mrad

---

## Identify & Understand Restrictions

- Documentation Research
- Optical Survey
- Lattice Modeling
  - LBNL study of AP2 chromaticity
- Instrumentation
- Beam Studies

## Mitigate

- Redesign/modify/rebuild specific elements
- Align/relocate specific elements

## Beam Based Alignment

- Lattice Model
- Instrumentation
- Orbit control
- Beam Studies

---

# Identifying Limitations and Lattice Models

# Identify Restrictions

## Building detailed lattice models

Tech Div has performed documentation research

Verifying drawings with components  
Produced tables of all apertures

*Final Checkout*

### Optical Survey

*Data 90% taken  
Crunch numbers*

Determine alignment of AP2 & Debuncher components  
Determine alignment of AP1, target hall & AP2

*Preparing to perform*

### Verify lattice parameters

Beam studies using upgraded instrumentation

## Models (OptiM & MAD)

*Continue to feed into models*

### Local & LBNL investigations

Identify restrictions and orbit control tolerances  
Propose resolutions

# MAD Model and Studies by LBNL

---



## AP2 Aperture Studies at LBNL

- Simulations to study effect of various machine errors and chromatic effects on acceptance
- Found **two possible causes of aperture restrictions**. Both have their root in the **large momentum spread of  $\pm 2.25\%$** :
  1. Residual **vertical dispersion** caused by misalignment of quadrupole magnets
  2. **Chromatic effects** due to large chromatic functions
- **Suggested experiments** for further study; a few mainly parasitic experiments have already been done, but **dedicated beam time** is required
- Studying possibilities to **reduce chromatic effects** by adding **sextupole magnets**


LBNL: I. Reichel, M. Placidi & M. Zisman

---

# MAD Simulations and Studies by LBNL




## Simulation Results



- Large **residual vertical dispersion** can create aperture problems in **small vertical apertures** at the end of the line

vertical phase space after AP2



- particles have initial offsets (no angles) corresponding to 0,  $\pm 12$ ,  $\pm 28$  and  $\pm 40 \pi \text{ mm mrad}$
- final amplitudes and phases **depend strongly on momentum deviation**




---

# Instrumentation

# Instrumentation Upgrades

## ■ Debuncher BPM system

- Old original electronics and Data Acquisition.
  - Reliability, maintenance and ease of use were issues
- New Electronics and Data Acquisition installed
  - 2.5MHz Closed Orbit system
  - (~50 $\mu$ m resolution)



Commissioned  
Making  
application user  
friendly

Example of  
difference orbit  
from local bump


# Instrumentation Upgrades

---

- **AP2 BPM system**
  - Want to make measurements using reverse protons
  - Old original electronics and Data Acquisition.
    - Reliability, maintenance and ease of use are issues
  - Desire  $<100\mu\text{m}$  resolution (53MHz)
    - Minimum is DAQ and software replacement
    - *Still* need to see if RF electronics are sufficient
  
- **Other**
  - Re-install AP2 709 horizontal collimator
    - Was re-installed; no beam studies yet
  - AP2 large aperture Toroid(s)
    - Beam intensity measurement along beam line
    - Started discussions with vendor
  - Study of whether to move SEMs

# AP2 BPM Beam Studies

- Observation of 53 MHz modulated reverse proton beam on AP2 BPMs
  - Good signal ( $\sim 5$  mV) on upstream (F27) BPMs
  - Injection kicker noise on downstream (AP50) BPMs



# Existing AP2 Instrumentation

System	Stacking	Rev. prot	Fwd. prot	Comment
BPMs (34)		Trying	Yes	Orig AM/PM Mod & DAQ 1/2 of system see kicker
BLMs (0)				System removed several years ago
SEMs (9)	Yes	Yes	Yes	Non-optimal phase advance between SEMs
Intensity (1)	Ion Chamber	Ion Chamber	Ion Chamber	Removed 3inch toroids from 6inch beam pipe
Collim. (5x2)	Yes	Yes	Yes	2 per transverse plane & 1 longitudinal sets
RF for BPMs	From MI	Commis. DRF1 53MHz	From MI	DRF1: Reverse adiabatic cavities curves to "bunch" beam

# Existing Debuncher Instrumentation

System	Stacking	Rev. prot	Fwd. prot	Comment
BPMs (120)		Yes <b>Yes</b>	Yes	<del>Orig AM/PM Mod &amp; DAQ</del> Hard to maintain & use <i>New System commissioned</i>
BLMs (62)	Not really	Yes	Yes	
Intensity (1)		DCCT	DCCT	Measures circulating current
Pickups (5)	Yes	Yes	Yes	2 are used for stacking TBT or studies "heater"
Collim.	Yes	Yes	Yes	1 scraper per plane
RF for BPMs		Re-comm. DRF3 2.5MHz	To be used	Studies RF system; new controls

---

# Known Restrictions & Steering Hazards

# Known Restrictions

---

## Band 4 cooling tanks arrays

Vertical array gaps were designed for  $\sim 30\pi$  mm-mrad

Determined that increasing the gap by 3.1mm can be done.

Will decrease frequencies of upper band of system to overlap with lower band; not affect overall cooling.

## Move DRF2 & DRF3 to low/zero dispersion region(s)

Radiation surveys show activation

-DRF3 has been re-located to low dispersion.

-Looking into different schemes of where to re-locate DRF2 and essential electronics.

## Other restrictions

*Identification and solutions may have to wait for modeling, beam studies and/or mitigation of other restrictions.*

Recently Identified Identified that the extraction kicker's elliptical pipe is  $22\pi$  mm-mrad aperture for off momentum particles.


---

Appears that inserting a rectangular beam pipe will

APs & Debuncher Acceptance - Keith Golwitzer



# Debuncher Extraction Kicker





82% of tracked beam particles inside of **current beam pipe (ellipse)**.

Rectangle of same inner dimensions accepts **91%**.

Increase horizontal dimension will accept **95%**: **Looking into offsetting pipe in kicker, but beam fairly small when extracting (good field region?)**

Will also motorize kicker stand to center beam pipe about beam.

# Limiting Apertures

Device	Horizontal		Vertical
			
Band 4 Hor. pickup	36.8 $\pi$	36.3 $\pi$	48.7 $\pi$
Band 4 Ver. pickup	40.5 $\pi$	39.0 $\pi$	29.9 $\pi$
Band 4 Hor. kicker	36.0 $\pi$	35.5 $\pi$	48.7 $\pi$
Band 4 Ver. kicker	41.2 $\pi$	41.1 $\pi$	30.1 $\pi$
Deb Extr. kicker	109.1 $\pi$	21.9 $\pi$	35.8 $\pi$

# Steering Restrictions

---

## Motorize stands for septum & kickers

Tolerances are small; desire to center devices  
Engineering will start by looking at existing  
tank motorized stands.

## Injection septum (common vacuum chamber)



Desire injected beam to be close to closed orbit  
Investigating whether spare can be reworked  
to minimize material at down stream end.

## D4Q4 replacement & BPM removal/relocation

~No vertical tolerance for injected beam  
2 large spare quad LQBs will replace quad;  
same integrated field and fits into space.  
Need stand work; have existing power supply.

*Change from build to  
using existing spares*

# D4Q4 Aperture



No tolerance for injected beam.

Will replace with two **large quad LQBs (pole tips drawn)**; increase vacuum chamber.

Move BPM from upstream area.

---

# Orbit Control


# Orbit Control

## AP2 Beam Line

*Started with  
4H+4V trims*

*Have added 1H+3V  
trims. Installed  
shunts on all  
dipoles of left  
bend*

Can add more  
trims as needed



# Orbit Control

Nearly finished with local  
bump commissioning

## Debuncher

Started with 13H+7V trims & a vert. plane motorized quad


Have added 5 two plane motorized quads (99)

➡ Added 10 two plane motorized quad stands (03)

Adding 20 two plane motorized quad stands (04)

Where the orbit  
control exists

No available  
space for trims;  
the ring is packed




Yellow: Dipole Trims

Blue: Motorized Quads



# Shutdown Work - Quad Stands





---

# Beam Based Alignment & Beam Based Determination of Apertures

# Beam Based Alignment

---

## Basic BBA Procedure

### Excite a quad

Most quads have shunts

### Measure response

BPM systems for proton studies


- A Debuncher pickup for AP2 during stacking

### Correct Orbit

Trims, shunts, motorized quad stands

# Debuncher Turn-By-Turn Instrumentation

Normally use Debuncher TBT with AP2 dipole trims and  
Injection elements to minimize injection oscillations



# Other Study Programs

---

Heat protons in Deb and watch BLMs

- Paint the Debuncher aperture

Prepare known emittance/momentum  
reverse proton beam & kick beam up

# Paint the Aperture

Not Fully debugged- commissioned in 1999-2000 for Debuncher.

For each corrector, kick until beam is extinguished: then have “painted” the aperture.

Program has no assumptions about beam emittance and distribution, so need to extinguish beam  $\Rightarrow$  each corrector reach is then only about  $\sim 4\pi$


Possible Solutions:

- 1) Be able to prepare beam to known emittance & distribution consistently before exciting any trim.
- 2) Use combinations of trims to map out more of the aperture.

The former needs much study time to see if possible;

the latter we have been pursuing...


AP2 & Debuncher Acceptance – Keith Gollwitzer




---

# Admittance Measurement Methods

# Admittance Measurements




Circulating Admittance  
 done by scraping heated  
 reverse proton beam:  
 Well defined edge and  
 extinction ( $\Delta p/p \sim 0$ )



Operational Admittance  
 done by scraping while  
 stacking: Hard to define  
 Beam edge & extinction  
 ( $\Delta p/p$  is full mom. spread)

# Admittance Measurements



Circulating Admittance  
done by scraping heated  
reverse proton beam:

Well defined edge and  
extinction ( $\Delta p/p \sim 0$ )



( $\Delta p/p$  is full mom. spread)

Old Method



# Operational Admittance Measurements

- Make separate (few minute setup) measurements of the beam edge and extinction point
  - lengthen the production cycle time to 10's seconds




Extinction Point: Schottkey power sampled seconds after injection versus Debuncher scraper; Spectrum Analyzer goes from flat line to small step in the 0.1box of left plot above

Beam edge: Run scraper into beam between cycles starting a few seconds after injection; record loss monitors as function of scraper position

# Momentum Acceptance

Longitudinal Schottky  
profile of  $\bar{p}$ 's filling  
the momentum  
aperture of the  
Debuncher.

Bunch rotation and  
stochastic cooling are  
off.



NOTE: An earlier (11/2002)  
measurement gives  
 $\Delta p/p = 4.6\%$

# Acceptance

	Measured AP2 + Debuncher (stacking)	Measured Debuncher (rev. prot.)	Smallest Aperture (lit. search)	Goal
Horizontal (mm-mrad)	$24 \pm 3 \pi$	$28 \pm 3 \pi$	$35.5 \pi$ { $22 \pi$ for off mom.}	$35 \pi$
Vertical (mm-mrad)	$18 \pm 2 \pi$	$20 \pm 2 \pi$	$30 \pi$	$35 \pi$
Momentum	$\pm 2.15\%$	$\pm 2.30\%$	--	$\pm 2.25\%$

---

# Beam Studies & Schedule

# Near Term Studies List

Gollwitzer Oct 28, 2003

## Commissioning/AP2&Debuncher Aperture Beam Studies

Current desired reverse protons studies are shown in the table below along with the needed preceding beam study, whether repeated injections are needed and total time (optimistic and disregards reverse proton setup time).

REVERSE PROTONS BEAM STUDY	PRECED. BEAM STUDY	REPEAT INJECT. (Y/N)	TOTAL TIME (HR)	% Done (Dec 15, 2003) % Done (Jan 23, 2004)
1. Measure transverse aperture & tunes on nominal orbit		No	1	100
2. Verify DRF3 bunches beam & measure Debuncher momentum aperture		No	1	100
3. Verify all new BPMs see intensity, record non-working BPMs; record nominal orbit and motorized quad stand read backs	2	No	1	100
4. Perform Debuncher 1 bumps using trims and record closed orbits	3	No	2	100
5. Create difference orbits and look for wrong BPM polarity; fix cabling	4	Offline & Access?	2	100
6. Each plane of each motorized quad stand: move known amount and record orbit	5	No	8	100
7. Off mom. meas. $\pm 1, \pm 2\%$ : DRF3 to move beam, mom. scrape, BPM orbit, measure tune, heat beam, transverse admittance meas.	5	No	6	
8. Develop bumps using trims and motorized quad stands; exercise/verify	6	No	16	40,60
9. Use Deb bumps to center beam in aperture	8	No	16	20
10. Kick beam up AP2; verify/record SEMs work and observe beam flag		Yes	1	
11. Setup DRF1 to provide 53MHz as beam is kicked up AP2	10	Yes	1	
12. Time-in upstream AP2 BPM DAQ; record several orbits	11	Yes	4	
13. Vary kick strength and observe beam flag, record SEMs and BPMs	12	Yes	1	
14. Vary septum strength, trims and left bend shunts; record SEMs and BPMs	12	Yes	4	
15. Repeat 11 for off mom. beam: (DRF1 freq.)	11	Yes	2	
16. DRF3 to change beam mom.; DRF1 bunch & kick beam up AP2; record BPMs & SEMs	15	Yes	8	
17. Center or record location of all Debuncher non-quad elements on motorized stands		No	16	
18. Sextuple determination of central freq.	2	No	4	
19. Validate 'Paint the Aperture' program	5	No	16	

Current desired stacking studies are shown in the table below along with the needed preceding beam study, the expected effect on stacking averages over the study period and total time (optimistic).

STACKING BEAM STUDY	PRECED. BEAM STUDY	EFFECT ON STACKING	TOTAL TIME (HR)	
20. Record SEMS and observe beam flag		Parasitic	1	100
21. Center beam in Lens and upstream quads; use SEMs and Debuncher TBT response	20	<25%	16	
22. Center beam in downstream quads and reduce trim dipole currents; use SEMs and Debuncher TBT response	21	<50%	16	5
23. Record AP2+Debuncher momentum acceptance (turn off RF and cooling)	20	Destructive	1	50
24. Measure AP2+Debuncher transverse admittances	20 & periodically	<50%	2	100
25. Exercise re-installed 709 collimator; monitor IC728, INJFLX, production eff	20	<50%	1	
26. Record SEM403 for closed orbit and injection orbit; latter uses Debuncher scraper	20	Destructive	1	
27. Record SEM403 & AP2 SEMs response to AP2 1-bumps; also observe beam flag	26	Destructive	4	10%
28. Set 719 collimators to select 0.5% slice of p/p about 0, $\pm 1, \pm 2\%$ : record momentum spectrum and measure transverse apertures	23 & 24	Destructive	16	
29. Record AP2 BPM response during stacking (intensity and/or position monitors?)	20	Parasitic	1	
30. Perform and record near-	20	<10%	8	50
31. Perform and record results of dispersion bumps in AP2	20	<50%	4	50
32. Optimize D:EKIK and horizontal bump settings	20 & 9	Parasitic	4	25
33. Optimize lens longitudinal position	22	Parasitic	2	

Not comprehensive. Written early Nov03, planned to complete within 6 months.

# Beam Studies Aug03-Feb04

**Reverse Proton Studies:**  
majority done during  
down periods or (recently)  
when have large stacks  
(4-6hr block of time).

Commission Debuncher BPM System	15hr
Commission Motorized Quad Stands	9hr
Commission Debuncher Local Bumps	36hr
Debuncher Orbit Correction	7hr
Paint the Aperture development	5hr
Reverse Protons into AP2, AP2 BPMs	6hr

**Stacking Studies:**  
depending upon study, 5%  
to 100% effect on stacking  
for short periods of time

AP2 $\pi$ bumps	8hr
Debuncher Turn-By-Turn	4hr
Admittance Measurement development	18hr

Aug- Sep	Nov	Dec	Jan	Feb
10hr	20hr	48hr	10hr	20hr

Total amount of time does not include end  
effects (reverse proton setup and recovery)

# Major Shutdown Work

---

## Shutdown 2004

- Install additional 20 motorized quad stands
- Replace D4Q4
- DRF2 Move

## Shutdown 2005

- Wider Band 4 vertical cooling arrays
- Upgraded Debuncher Injection Septum (SD2004 ? )
- Motorized stands for Debuncher injection & extraction kickers
- Possible modifications to Debuncher extraction kicker (SD2004 ? )
- Possible implementation of AP2 chromatic correction

## Shutdown 2006

- New Debuncher extraction kicker (if not modified during SD2005)
- Implement of AP2 chromatic correction (if not implemented during SD 2005)

## Summary

---

Beam Based Alignment will do the job:

Upgrade instrumentation

Better orbit control

AP2 beam line

Had 13 knobs, have added 10, can add a few more

Debuncher ring

Had 21 knobs, have added 30, will add 40 more

As understanding of the lattices improve

so do the physical apertures & tolerances

Upgrade/new software applications

Will mitigate limiting apertures

Redesign/modify/rebuild/relocate

AP2 & Debuncher acceptance - Keith Schwirzer